

IITMRP - PHASE - 2

REPAIRS TO 'C' -SECTIONS IN THE ROOF OF B BLOCKS AT TERRACE LEVEL AND 3 RD FLOOR LEVEL AND FLOOR TILE WORK AT C & D BLOCKS

BOQ

SI No	Item Description	Unit	Qty	Rate	Amount
1	Removing the existing sealants in the joints of 'C' Sections, roughening the exposed surface to have effective bond to new concrete, applying neto bond or equivalent chemical in the quantity recommended by the manufacturers after cleaning the surface as recommended, providing and filling approved make of micro concrete of the required quantity, finishing the surface smooth, curing the same for a minimum period of 7 days including supply, installing, operating , dismantling and clearing from site of Gondola of required size with necessary safety certificate etc complete	Meter	300		0
2	Supply , delivery and applying one coat of Brush bond of Fosroc or equivalent make including necessary cleaning etc complete.	Meter	300		0
3	Painting concrete surface with two or more coats using approved make, colour and texture paint over a coat of approved primer after finishing the surface with two coats of external approved make putty complete	Sqm	600		0
4	Providing and laying vitrified floor tiles in of size 600x600 MM of thickness 6 MM to be with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:3 (1 cement : 3 sand), jointing with grey cement slurry @ 3.3 kg/ sqm including spacers and grouting the joints with special chemical grout complete and removing exisintg floor tile with mortar	Sq.m	60		0
Total					0

1. GST will be paid extra as per prevailing rates.
2. The work should be started immediately on award and completed with in 7 days of date of award.
3. All safety measures including wearing PPE should taken while carrying out the work
4. Workers will not be permitted to stay in the campus.
- 5..The various instructions of the Government including the SOP should be strictly followed while carrying out the work
6. Workers will be tested while entering the campus and any one with fever will not be pemitted to enter the campus
7. Hand sanitization arrangment should available at site of work.
8. All workers and supervisor should wear face masks at all times
9. TDS at the prescribed rates shall be deducted from the bills.